

ALL MODELS · SLATE · ONYX · EMBER

Specifications

Every pod is built in Moorebank, NSW on a registered 3.5-tonne trailer base and arrives complete and pre-plumbed. Figures are nominal; a licensed electrician and plumber complete the final connections on site.

At a glance

	SLATE 01	ONYX 02	EMBER 03
PRICE FROM	\$65,000	\$55,160	\$65,000
LAYOUT	Kitchenette	Kitchenette	Full kitchen
EXTERNAL (L×W×H)	6.00 × 2.40 × 2.77 m	5.80 × 2.77 × 2.77 m	6.00 × 2.40 × 2.77 m
FLOOR AREA	≈ 14.4 m²	≈ 16.0 m²	≈ 14.4 m²
CAPACITY	1–2 person	1–2 person	1–2 person
INTERNAL (L×W×H)	5.80 × 2.30 × 2.65 m	5.50 × 2.55 × 2.40 m	—
FRIDGE	90 L provision	90 L provision	90 L provision
BED	Queen + pocket spring mattress	Queen + pocket spring mattress	Queen + pocket spring mattress, under-bed drawers
KITCHEN	Base cabinet, natural granite counter-top, induction cooker, sink + mixer	Base cabinet, natural granite counter-top, induction cooker, sink + mixer	Full kitchen — induction, sink, overhead + base cabinetry
BATHROOM	Ensuite — shower, basin, flush WC + macerator or composting WC	Ensuite — shower, basin, flush WC + macerator or composting WC	Ensuite — shower, basin, flush WC + macerator or composting WC
DESK / STORAGE	Shoe rack + wardrobe	Wardrobe	Collapsible work desk, shoe rack + wardrobe
TRAILER BASE	3.5 tonne registered	2.5 tonne non-towable	3.5 tonne registered
UNIT WEIGHT	≈ 3 t	≈ 2 t	≈ 3 t
APPROVAL	No approval*	No approval*	No approval*
WARRANTY	5 yr structural	5 yr structural	5 yr structural

Construction

Common to all three models unless noted.

STRUCTURE	RHS galvanised steel frame on a trailer base — 3.5 tonne registered on Slate and Ember, 2.5 tonne non-towable on Onyx
WALLS	50 mm interlocking EPS sandwich panel, or RHS steel frame with metal / WPC cladding outside and cladding or plasterboard + paint inside
CLADDING	Colorbond® corrugated steel with WPC composite accents (graphite on Slate, all-black on Onyx, black + timber on Ember)
ROOFING	Colorbond® corrugated metal deck with 35 mm EPS core
INSULATION	R2.5 rockwool — walls & floor · R4.0 rockwool — roof
SUBFLOOR	17 mm marine plywood or waterproofed MgO panel, screwed to the subfloor
FLOORING	Vinyl or 5 mm SPC hybrid timber
WALL LINING	9 mm engineered waterproof composite panel or 9 mm plywood
WINDOWS & DOORS	1.4 mm aluminium-framed, double-glazed tempered glass, flyscreens
SHOWER CABIN	8 mm tempered glass with ABS shower tray, hot & cold mixer
FURNITURE	18 mm moisture-resistant MFC
ELECTRICAL & PLUMBING	Compliant with Australian safety standards and regulations

Fitted as standard

Slate

MODEL 01 · KITCHENETTE

- 3.5 tonne trailer base
- Reverse-cycle 2.5 kW air-conditioning
- Queen-sized bed + pocket spring mattress
- Shoe rack and wardrobe
- Kitchen — base cabinet, natural granite countertop, induction cooker, sink + mixer
- 90 L fridge provision
- Shower cabin, 8 mm tempered glass
- 16 L continuous gas water heater
- Wash basin and cabinet with mirror
- Flush toilet + macerator (to 30 m) or composting toilet
- 5 mm SPC hybrid flooring
- Aluminium profile LED strip light, 4 × 10 A power sockets

Onyx

MODEL 02 · KITCHENETTE

- 2.5 tonne non-towable trailer base
- Reverse-cycle 2.5 kW air-conditioning
- Queen-sized bed + pocket spring mattress
- Wardrobe
- Natural granite countertop kitchenette — induction cooker, single-bowl steel sink + mixer
- 90 L fridge provision
- Shower cabin, 8 mm tempered glass
- 16 L continuous gas water heater
- Wash basin and cabinet with mirror
- Flush toilet + macerator (to 30 m) or composting toilet
- 5 mm SPC hybrid flooring
- LED oyster lights, 4 × 10 A power sockets

Ember

MODEL 03 · FULL KITCHEN

- 3.5 tonne trailer base
- Reverse-cycle 2.5 kW air-conditioning
- Queen bed + pocket spring mattress, under-bed drawers
- Shoe rack and wardrobe
- Full kitchen — induction cooker, sink, overhead and base cabinetry
- 90 L fridge provision
- Shower cabin, 8 mm tempered glass
- 16 L continuous gas water heater
- Wash basin and cabinet with mirror
- Flush toilet + macerator (to 30 m) or composting toilet
- 5 mm SPC hybrid flooring
- Aluminium profile LED strip light, 4 × 10 A power sockets
- Collapsible work desk

Services & site requirements

Final connection

Arrives complete and pre-plumbed. A licensed electrician and plumber finish the electrical and water connections; a guide and video are supplied.

Waste

Choose a flush WC on a macerator pump up to 30 m to the connection point or a composting toilet, which needs no sewer connection at all.

Hot water

16 L continuous-flow gas water heater, fitted.

Access

Built on a registered trailer and towed to your site, then positioned safely where access allows.

Options, delivery & terms

Pergola with deck

6.0 × 2.4 m — \$18,999

Delivery

Free within 100 km of Sydney and Brisbane; quoted per km beyond that, plus on-site setup.

Deck only

3.0 × 2.9 m — \$6,999

Deposit

\$1,000 secures your build. Balance plus delivery due before dispatch; no refunds on deposits after 24 hours.

Inspection

By appointment in Moorebank, and before delivery if wanted.

Warranty

5 years on structural integrity and major components. Appliances and equipment follow their manufacturers' warranties.

Tiny Down Under Pty Ltd — Moorebank, NSW ·
tdaustralia@gmail.com · 0429 790 464

Prices in AUD, excluding GST, ex delivery & on-site setup.
Specifications subject to change.